

Certificate No:	C4TM - 000091	Issued:	2 April 2009
------------------------	----------------------	----------------	---------------------


Issued to:
Besblock Limited
Heslop
Halesfield Industrial Estate
Telford
Shropshire
TF7 4NF
Tel: 01952 685000

General Construction Specification: (see detail below for full construction)	Load bearing, Inner Leaf:	100mm Star Performer Block
	Insulation:	100mm fullfill Mineral Wool
	Cavity:	100mm fullfill
	Cladding, Outer Leaf:	103mm brick


Description:	Ground Floor, Timber Suspended Floor
Reference:	Accredited Detail MCI-GF-03

Junction Detail

Ensure insulation is in contact with the underside of the timber flooring. ①
Pack gap between floor joist and blockwork wall with compressible insulation if over 25mm otherwise inject an insulating expanding foam. ②
If compressible insulation is installed, ensure that full insulation depth is achieved between floor joists by fixing netting to sides of joists with battens. ③



Accredited (Indicative) Detail Number: MCI-GF-03



Temperature Distribution

Linear Thermal Transmittance
W/m.K

$\Psi = 0.160$

Temperature Factor³ for
Humidity and Mould

$f = 0.816$

Calculation Prepared By: **Matthew Wright MA Physics (Oxon) PGCE**

Notes:

- Ψ and f are only valid for the detail drawn and described above.
- U-values for the flanking walls are within the range $U = 0.28 \text{ W/m}^2\cdot\text{K}$ or less.
- In dwellings, a temperature factor f that is >0.75 would avoid the risk of mould growth.
- Calculations have been performed in accordance with:
 - EN ISO 10211_2007 (British Standards)
 - IP 1/06 & BR497 (BRE Press)
 and with reference to the following publications:
 - EN ISO 6946 (British Standards)
 - BR443 (BRE Press)